


NOTES

1. All footings shall be 309kg/M³-C-22-Mpa (520-C-2500) concrete.
2. The following items shall be furnished and installed only when shown on the plans and/or called for in the special provisions.
 - a. Barbed Wire
 - b. Extension Arm
 - c. Top Horizontal Rail
3. Chain link fence shall conform to Section 206-6 of the Standard Specifications for Public Works Construction unless specifically noted on this drawing.
4. See Standard Drawing M-20 for additional details.

EXTENSION ARM AND BARBED WIRE

LEGEND ON PLANS



| Revision | By | Approved | Date |
|------------|----|-------------|-------|
| ORIGINAL | | A.Kercheval | 12/75 |
| Add Metric | | T. Stanton | 03/03 |
| | | | |
| | | | |

SAN DIEGO REGIONAL STANDARD DRAWING

CHAIN LINK FENCE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

T. Stanton 3/10/2003
 Chairperson R.C.E. 19246 Date

DRAWING NUMBER M-6